

# **REGULATED MARKET COMMITTEE**

## **KENDRAPARA**

### **DETAIL TENDER SCHEDULE**

**Name of the Work :**

**Construction of different Developmental  
Works at Chhata Hat under RMC  
Kendrapara**

**OFFICE OF THE REGULATED MARKET COMMITTEE  
KENDRAPARA**

**At/PO-Jamadhar, Dist.-Kendrapara**

**TENDER SCHEDULE**

Name of the Work	:	Construction of different developmental works at Chhata Hat under RMC Kendrapara
Tender Cost	:	Rs.25,57,197.00
Tender paper Cost + 5% VAT	:	Rs.6,300.00
E.M.D. @ 1%	:	Rs.25,572.00
Class of Contractor	:	'B' & 'A'
Period of Completion	:	120 days
Date of Display of Tender Paper	:	03-02-2014
Date & Time of receive of Tender Paper	:	Up to 4 P.M. on 13-02-2014
Date of Opening	:	14-02-2014 at 3 P.M.

**OFFICIAL USE ONLY**

Sold for the work .....

Class ..... At .....

P.O. ....

***Signature of Issuing Officer***

**TERMS AND CONDITIONS**

1. The tender may not be accepted by the competent authority unless accompanied by attested copies of VAT C.C., Income Tax clearance certificate / PAN requisite EMD and valid registration certificate.
2. Tenders in all complete shape must be accompanied with attested copies of valid registration certificate, PAN Card, VATCC, along with Draft/Pay order towards purchase of Tender Paper & required EMD in shape of Demand Draft / Pay order in favour of RMC Kendrapara. Tender without required EMD will be liable for rejection.
3. In case of less quoted tenders, the Tenderer has to deposit the differential amount (between the tender cost and quoted cost) at the time of submitting tender paper for additional performance security in shape of Demand Draft / Pay order in favour of RMC Kendrapara. In case of non-submission of differential amount at the time of submitting tenders the tender shall be treated as rejected. Any undertaking for extension of time in this regard will never be entertained.
4. Each tender shall be accompanied by original affidavit regarding authentication of documents furnished by the tenderer failing which tender will be liable for rejection.
5. The successful bidder is required to deposit @ 1% I.S.D. before accepted agreement.
6. The contractor should abide by the fair wages clause introduced by Govt. and shall not pay dues less than the fair wages fixed by the Govt. time to time to the labourer engaged by him in the work.
7. All the tenders received will remain valid for a period of 90 (ninety) days from the date of receipt of tenders. Subsequently the period of validity can be extended with consent, by tenderer as well as the Chairman RMC.
8. The right is reserved to make such increase or decrease in quantities of items of work mentioned in the schedule attached to the tender notice as may be considered necessary for satisfactory completion of the contract work and such increase or decrease shall not be entitled to any compensation and this account except extension of time where considered necessary. Right is also reserved to omit any items of works included in the tender schedule as is considered necessary and the contractor shall not be entitled to any compensation on this account.

9. Item or work not covered in the tender schedule shall be paid at current schedule of rates and those not covered in the said schedule of rates will be paid on actual analysis or quotation approved by the Chairman RMC or on deviation from the quoted rates.
10. On no account the contract work should be sublet to any body without prior approval of the competent authority of the department and in such an event the contract may be rescinded.
11. No compensation for any damage done by rains or by similar action during the execution of work will be paid.
12. The contractor shall make at his own cost housing accommodation and medical aid to the labourers engaged in the work.
13. The contractor shall make arrangement at his own cost at the work site for proper storage of the materials made over to him.
14. The tender, which is not in the prescribed proforma & not strictly according to the terms and conditions of the tender call notice and specification, is liable for rejection.
15. As regards extra items of work besides the schedule of quantities written order must be obtained from the Engineer-in-charge before the work is taken up.
16. The contractor is to supply necessary labourer and materials, for the purpose of alignment, layout and profiling whenever required at his own cost.
17. The tenderers are required to go through each clause of RMC Form No.2 carefully in addition to clauses mentioned herein before tendering for the work.
18. Approach road to the site will be made and maintained by the contractor at his own cost & responsibility for which no payment will be made by the Department.
19. All the materials required for bonafide use in the work, depending on the description of the departmental authority will be supplied by the contractor only. The materials will be carried to site of work by the contractor at his own cost. Before procuring the materials, the contractor should take clearance from the Engineer-in-charge and the materials produced by him should be got approved by the Engineer-in-charge before use. No departmental materials will be issued to the contractor.
20. Dewatering & coffer damming and diversion arrangement for drain water & road if required during execution will be done by the contractor at his own cost and responsibility.

21. Water for execution will be arranged by the contractor at his own cost & responsibility.
22. Concrete should be vibrated with skin vibrator or pan-vibrator as per required at contractor's own cost.
23. The contractor is entitled to pay only at the rates quoted by him and enter in the agreement. If the contractor is required to do any ancillary work for doing the main work as per the contract, it will be entirely to his account and nothing extra over and above the agreement rates will be paid.
24. The contractor will make his own arrangements to watch the materials at site at his own cost till the work is finally closed and handed over.
25. Any damage caused to the work due to any cause what so ever during the execution will be made rectified by the contractor until is handed over to the department in complete shape "Any cause" includes natural calamities of all kinds.
26. If the proportionate progress will not show with 15 days from the date of commencement of the work, the contract is liable to be closed as per relevant penal clause of the F-2 agreement.
27. All conditions, special conditions put forth by the tenderer / contractor before or after execution of this agreement whether submitted along with the tender or before or after shall automatically stand rejected and superseded by the terms and conditions of this agreement / DTCN. The terms and conditions of the DTCN shall form part of the agreement. In case of any conflict, the terms of agreement and DTCN will prevail.
28. Over and above to this condition the terms & conditions and rules and regulations as laid down Odisha. Detailed Standard Specifications are also binding on the part of this contract.

## Construction of different developmental works at CHHATA under R.M.C. Kendrapara

**Tender Value : Rs.25,57,197.00**

Sl. No.	Item of Work	Unit	Qty.	Rate in Figure (In Rs..p)
1.	Earth work excavation in foundation in hard soil with all lead and lift including dressing and leveling the bed and depositing the excavated earth at place away from work site with all lead and lifts including dewatering and T & P required for the work etc. complete and directed by Engineer-in-charge.	Each Cum	78.10	87.55
2.	Filling foundation and plinth with sand well watered and rammed layers with all leads and lifts etc. complete as directed by Engineer-in-charge.	Each Cum	26.03	352.25
3.	Cement Concrete (1:3:6) in foundation and floors using 4 cm size hard black crusher broken granite metal of approved quality from approved quarry including hoisting, lowering and laying concrete layers not exceeding 15cm thick to the required level, ramming, watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalties and labour with T & P required for the work etc. complete including dewatering if required.	Each Cum	18.67	3981.78
4.	Cement Concrete (1:2:4) using 12mm size hard black granite crusher broken chips with cost and conveyance of all materials and labour with T & P required for the work with royalties, taxes complete in all floors.	Each Cum	7.50	5197.00

5.	K.B. brick masonry in Cement Mortar (1:6) in Foundation and Plinth of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling, watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc. complete.	Each Cum	94.89	3744.15
6.	K.B. brick masonry in Cement Mortar (1:6) in super structure of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling, watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc. complete.	Each Cum	107.74	3777.48
7.	R.C.C. M-20 using 20mm and 10mm size hard black crusher broken granite chips of approved quarry including hoisting, lowering and laying compacting concrete in Roof Slab, column & Beam, Lintel, Plinth Bend, Wall Bend etc. including all R.C.C. works with necessary slope and smooth to receive tar felting or tracing, watering and curing for four weeks, providing grooves or beds and fan hooks as per requirement in ceiling, where necessary including cost, conveyance, taxes and royalty of all materials and labour with T & P required for the work etc. complete in all respect but excluding cost of Tor Steel and binding wires of 18 to 20 gauge and labour charges for straightening bending etc. and including cantering, shuttering etc. complete.			

(A)	Column Base and Plinth Band	Each Cum	32.77	5293.67
(B)	Column and Beam	Each Cum	15.79	10672.18
(C)	Slab / Fin	Each Cum	2.39	6897.69
8.	Supplying, fitting and fitting of Angle framed flat iron made Grill Gate including priming.	Each Kg.	340.00	65.00
9.	Painting two coats with approved quality of weather coat with cost, conveyance, taxes with a coat of cement wash.	Each Sqm.	1411.38	54.86
10.	Painting two coats with approved quality of enamel paint with cost, conveyance, and taxes.	Each Sqm.	515.59	87.86
11	Straightening bend up or coiled rods, Tor rods, cutting, bending, cracking, hooking welding or jointing (if required) the "tor Steels rods" & binding wire and tying the grills hoisting laying and placing in proper position as required for RCC works for providing if an hooks including cost, conveyance and taxes of Tor Steel and binding wire of 18 to 20 gauge and labour with T & P required for the work etc. complete in all respect in all floors (weight of the binding wire will not be considered for payment) complete.	Each Qntl.	45.00	6483.78



12.	12mm thick cement plaster with cement mortar (1:6) to brick masonry after racking out joint to finished smooth watering & conveyance of all materials and labour with T & P required for the work with all taxes royalty etc. complete.	Each Sqm.	906.90	84.69
13.	Filling F & P with excavated materials.	Each Cum	78.10	48.64
14.	Scraping of old plaster and cleaning of debris from roof / ceiling / wall surface.	Each Sqm.	1981.56	18.25
15.	6mm thick cement plaster with Cement Mortar (1:4) over RCC surface after racking out joints to finished smooth watering and conveyance of all materials and labour with T & P required for the work with all taxes royalty etc. complete.	Each Sqm.	747.80	91.65
16.	4cm thick grading concrete with C.C. (1:2:4) using 12mm & down grade size HBGCB chips with cost, conveyance and royalty.	Each Sqm.	1450.90	369.62
17.	Dismantling of R.C.C. work including cleaning and shuttering of debris etc. complete.	Each Cum	2.39	542.98

18.	Colour washing two coats with approved cement paint over one coat of cement wash over surface of the wall including all labour charges cost and conveyance of all materials, royalties, taxes & T & P etc. complete. (including cost of materials)	Each Sqm.	2198.48	35.77
19.	Cement punning over new plastered surface with cost, conveyance and royalty.	Each Sqm.	50.00	20.22
20.	Dismantalling, repairing and refitting of rolling shutter including providing required petty spares, fabrications.	Each No.	34.00	2000.00

(Total 20 items) only

**No. of Corrections :**

**No. of Overwritings :**

**Junior Engineer  
OSAM Board, Bhubaneswar**

**Asst. Engineer  
OSAM Board, Bhubaneswar**

**Secretary  
RMC Kendrapara**

**Chairman  
RMC Kendrapara**