

REGULATED MARKET COMMITTEE

KENDRAPARA

DETAIL TENDER SCHEDULE

Name of the Work :

**Construction of different Developmental
Works at M.M.Y. Jamadhar**

**OFFICE OF THE REGULATED MARKET COMMITTEE
KENDRAPARA**

At/PO-Jamadhar, Dist.-Kendrapara

TENDER SCHEDULE

Name of the Work	:	Construction of different developmental works at M.M.Y. Jamadhar
Tender Cost	:	Rs.58,44,277.00
Tender paper Cost + 5% VAT	:	Rs.10,500.00
E.M.D. @ 1%	:	Rs.58,450.00
Class of Contractor	:	'B' & 'A'
Period of Completion	:	8 months
Date of Display of Tender Paper	:	03-02-2014 to 12-02-2014
Date & Time of receive of Tender Paper	:	Up to 4 P.M. on 13-02-2014
Date of Opening of Tender	:	14-02-2014 at 3 P.M.

OFFICIAL USE ONLY

Sold for the work

Class At

P.O.

Signature of Issuing Officer

TERMS AND CONDITIONS

1. The tender may not be accepted by the competent authority unless accompanied by attested copies of VAT C.C., Income Tax clearance certificate / PAN requisite EMD and valid registration certificate.
2. Tenders in all complete shape must be accompanied with attested copies of valid registration certificate, PAN Card, VATCC, along with Draft/Pay order towards purchase of Tender Paper & required EMD in shape of Demand Draft / Pay order in favour of RMC Kendrapara. Tender without required EMD will be liable for rejection.
3. In case of less quoted tenders, the Tenderer has to deposit the differential amount (between the tender cost and quoted cost) at the time of submitting tender paper for additional performance security in shape of Demand Draft / Pay order in favour of RMC Kendrapara. In case of non-submission of differential amount at the time of submitting tenders the tender shall be treated as rejected. Any undertaking for extension of time in this regard will never be entertained.
4. Each tender shall be accompanied by original affidavit regarding authentication of documents furnished by the tenderer failing which tender will be liable for rejection.
5. The successful bidder is required to deposit @ 1% I.S.D. before accepted agreement.
6. The contractor should abide by the fair wages clause introduced by Govt. and shall not pay dues less than the fair wages fixed by the Govt. time to time to the labourer engaged by him in the work.
7. All the tenders received will remain valid for a period of 90 (ninety) days from the date of receipt of tenders. Subsequently the period of validity can be extended with consent, by tenderer as well as the Chairman RMC.
8. The right is reserved to make such increase or decrease in quantities of items of work mentioned in the schedule attached to the tender notice as may be considered necessary for satisfactory completion of the contract work and such increase or decrease shall not be entitled to any compensation and this account except extension of time where considered necessary. Right is also reserved to omit any items of works included in the tender schedule as is considered necessary and the contractor shall not be entitled to any compensation on this account.

9. Item or work not covered in the tender schedule shall be paid at current schedule of rates and those not covered in the said schedule of rates will be paid on actual analysis or quotation approved by the Chairman RMC or on deviation from the quoted rates.
10. On no account the contract work should be sublet to any body without prior approval of the competent authority of the department and in such an event the contract may be rescinded.
11. No compensation for any damage done by rains or by similar action during the execution of work will be paid.
12. The contractor shall make at his own cost housing accommodation and medical aid to the labourers engaged in the work.
13. The contractor shall make arrangement at his own cost at the work site for proper storage of the materials made over to him.
14. The tender, which is not in the prescribed proforma & not strictly according to the terms and conditions of the tender call notice and specification, is liable for rejection.
15. As regards extra items of work besides the schedule of quantities written order must be obtained from the Engineer-in-charge before the work is taken up.
16. The contractor is to supply necessary labourer and materials, for the purpose of alignment, layout and profiling whenever required at his own cost.
17. The tenderers are required to go through each clause of RMC Form No.2 carefully in addition to clauses mentioned herein before tendering for the work.
18. Approach road to the site will be made and maintained by the contractor at his own cost & responsibility for which no payment will be made by the Department.
19. All the materials required for bonafide use in the work, depending on the description of the departmental authority will be supplied by the contractor only. The materials will be carried to site of work by the contractor at his own cost. Before procuring the materials, the contractor should take clearance from the Engineer-in-charge and the materials produced by him should be got approved by the Engineer-in-charge before use. No departmental materials will be issued to the contractor.
20. Dewatering & coffer damming and diversion arrangement for drain water & road if required during execution will be done by the contractor at his own cost and responsibility.

21. Water for execution will be arranged by the contractor at his own cost & responsibility.
22. Concrete should be vibrated with skin vibrator or pan-vibrator as per required at contractor's own cost.
23. The contractor is entitled to pay only at the rates quoted by him and enter in the agreement. If the contractor is required to do any ancillary work for doing the main work as per the contract, it will be entirely to his account and nothing extra over and above the agreement rates will be paid.
24. The contractor will make his own arrangements to watch the materials at site at his own cost till the work is finally closed and handed over.
25. Any damage caused to the work due to any cause what so ever during the execution will be made rectified by the contractor until is handed over to the department in complete shape "Any cause" includes natural calamities of all kinds.
26. If the proportionate progress will not show with 15 days from the date of commencement of the work, the contract is liable to be closed as per relevant penal clause of the F-2 agreement.
27. All conditions, special conditions put forth by the tenderer / contractor before or after execution of this agreement whether submitted along with the tender or before or after shall automatically stand rejected and superseded by the terms and conditions of this agreement / DTCN. The terms and conditions of the DTCN shall form part of the agreement. In case of any conflict, the terms of agreement and DTCN will prevail.
28. Over and above to this condition the terms & conditions and rules and regulations as laid down Odisha. Detailed Standard Specifications are also binding on the part of this contract.

Construction of different developmental works at M.M.Y. Jamadhar under R.M.C. Kendrapara

Tender Value : Rs.58,44,277.00

Sl. No.	Item of Work	Unit	Qty.	Rate in Figure (In Rs..p)
1.	Earth work excavation in foundation in hard soil with all lead and lift including dressing and leveling the bed and depositing the excavated earth at place away from work site with all lead and lifts including dewatering and T & P required for the work etc. complete and directed by Engineer-in-charge.	Each Cum	246.91	87.55
2.	Filling foundation and plinth with sand well watered and rammed layers with all leads and lifts etc. complete as directed by Engineer-in-charge.	Each Cum	744.14	278.52
3.	Filling of excavated materials in foundation and plinth including all cost of labour etc. as direction of Engineer-in-charge etc. complete.	Each Cum	242.32	48.64
4.	Cement Concrete (1:3:6) in foundation and floors using 4 cm size hard black crusher broken granite metal of approved quality from approved quarry including hoisting, lowering and laying concrete layers not exceeding 15cm thick to the required level, ramming, watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalties and labour with T & P required for the work etc. complete including dewatering if required.	Each Cum	111.95	3996.81

5.	Dismantling and removing of old damaged C.C. work with shifting of debris.	Each Cum	25.99	271.49
6.	K.B. brick masonry in Cement Mortar (1:6) in Foundation and Plinth of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling, watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc. complete.	Each Cum	146.40	3691.51
7.	R.C.C. M-20 using 20mm and 10mm size hard black crusher broken granite chips of approved quarry including hoisting, lowering and laying compacting concrete in Roof Slab, column & Beam, Lintel, Plinth Bend, Wall Bend etc. including all R.C.C. works with necessary slope and smooth to receive tar felting or tracing, watering and curing for four weeks, providing grooves or beds and fan hooks as per requirement in ceiling, where necessary including cost, conveyance, taxes and royalty of all materials and labour with T & P required for the work etc. complete in all respect but excluding cost of Tor Steel and binding wires of 18 to 20 gauge and labour charges for straightening bending etc. and including cantering, shuttering etc. complete.			
(A)	Column Base and Plinth Band	Each Cum	56.76	5307.67
(B)	<u>Column and Beam</u>			
(i)	Upto 3 Mtr. Height	Each Cum	16.97	10686.27

(ii)	Above 3 Mtr. Height	Each Cum	16.20	11876.14
(C)	Lintel / Wall Band	Each Cum	20.45	6911.78
(D)	Staircase / Landing / Step	Each Cum	1.63	7679.74
(E)	Roof Slab	Each Cum	21.81	7679.74
8.	Straightening bend up or coiled rods, Tor rods, cutting, bending, cracking, hooking welding or jointing (if required) the "tor Steels rods" & binding wire and tying the grills hoisting laying and placing in proper position as required for RCC works for providing if an hooks including cost, conveyance and taxes of Tor Steel and binding wire of 18 to 20 gauge and labour with T & P required for the work etc. complete in all respect in all floors (weight of the binding wire will not be considered for payment) complete.	Each Qntl.	117.00	6480.13
9.	Dismantling of brick work including cleaning of debris.	Each Cum	0.08	509.64
10.	Cement Concrete (1:2:4) using 12mm size hard black granite crusher broken chips with cost and conveyance of all materials and labour with T & P required for the work with royalties, taxes	Each Cum	64.21	5211.09

	complete in all floors.			
11.	K.B. brick masonry in Cement Mortar (1:6) in super structure of approved size and quality 3splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling, watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc. complete.			
(A)	Up to 3 Mtr. Height	Each Cum	130.13	3724.84
(B)	Above 3 Mtr. Height	Each Cum	144.33	3844.04
12.	12mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering & conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.			
(A)	Up to 3 Mtr. Height	Each Sqm.	1331.23	83.58
(B)	Above 3 Mtr. Height	Each Sqm.	1023.66	118.89
13.	16mm thick cement plaster with Cement Mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all material and labour with T & P required for the	Each Sqm.	133.20	114.64

	work with all taxes royalty etc. complete.			
14.	Supplying, fitting, fixing of MS shutter with frame with M.S. angle of (35 x 25 x 6)mm and shutter section of 30 x 30 x 5mm with welding of 25 x 6mm flat & welding of 16 gauge CR sheet with arrangement of clamp, fitting of 3 nos. 4" hinges, 1 no. of 2" hinges and 300mm x 16mm M.S. Aldrop with 8" tower bolt including cost, conveyance, taxes of all materials labour T & P etc. required for the complete in all respect etc.	Each Kg.	490.00	75.00
15.	6mm thick cement plaster with Cement Mortar (1:4) over RCC surface after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.	Each Sqm.	136.80	91.09
16.	Supplying, fitting, fixing of M.S. Steel ventilator glazed composite with M.S. grill outside iron frame welded with wire netting or mesh with glass pairs including supplying & fixing of putting & wire clips, screw & cost of materials including all cost conveyance etc.	Each Sqm.	12.00	2391.65
17.	Supplying and conveyance at site M.S. angular / Tubular Truss, purlins of approved size as per design in all round well finished bonds provide erecting, fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M.S. members and labour for welding etc. and fixing complete materials used in the work shall confirm	Each Qntl.	56.20	8423.00

	to relevant I.S. specification.			
18.	Painting two coats with approved enamel paints over new iron/wood works including cost of materials, labour and T & P etc. complete as directed by Engineer-in-charge (including cost of paints primer etc.)	Each Sqm.	314.96	116.05
19.	Supplying, fitting & fixing of G.C.I. sheets for roofing of ISI mark (40mm) including fitting, fixing of ridges and wind ties, J-hooks with washer, earned of materials as per directed of Engineer-in-charge including all costs of materials, G.C.I. sheets and labour charges etc. fitting materials, taxes, T & P charges (but excluding wind ties) etc. complete.	Each Sqm.	526.00	397.36
20.	20mm thick grading plaster with C.C. (1:4) over roof slab with cost, conveyance and royalty.	Each Sqm.	174.62	141.79
21.	Supplying, fitting & fixing of HD bolts size 0.60m long with 15 x 15 x 4 mm base plate fixing in cement concrete (1:2:4) including all cost of materials and labour etc. complete.	Each Kg.	200.00	65.00
22.	Supplying and conveyance at site MS flat iron wind ties of size 35 x 5mm all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all MS members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant ISI specification.	Each Kg.	320.00	60.00

23.	Colour washing two coats with approved cement paint over one coat of cement wash over surface of the wall including all labour charges cost and conveyance of all materials, royalties, taxes & T & P etc. complete. (including cost of materials)	Each Sqm.	1138.80	35.77
24.	Providing anti-termite treatment with approved quality of chemical with cost, conveyance and royalty.	Each Sqm.	50.00	64.99
25.	Supplying, fabricating of angle framed and flat / square bar made Grills for main gate / D & W / Boundary top etc. complete.	Each Kg.	3225.00	75.00
26.	Colour washing two coats with approved quality of weather coat over one coat of cement wash over surface of the wall including all labour charges cost and conveyance of all materials, royalties, taxes and T & P etc. complete (including cost of materials)	Each Sqm.	1750.21	42.32
27.	Cost of Fire Extinguisher of ISI marked of 4 Kg. with cost conveyance & taxes.	Each No.	2.00	9000.00

(Total 27 items) only

No. of Corrections :

No. of Overwritings :

**Junior Engineer
OSAM Board, Bhubaneswar**

**Asst. Engineer
OSAM Board, Bhubaneswar**

**Secretary
RMC Kendrapara**

**Chairman
RMC Kendrapara**